

GOVT. OF ASSAM
OFFICE OF THE DISTRICT COMMISSIONER:::CACHAR:::SILCHAR
(CONSTRUCTION/STRONG ROOM/ELECTRIFICATION /WATER SUPPLY CELL)
MUNICIPAL ELECTION- 2026

No.CEL/SMC/C&E CELL(TENDER)/2026/06

Dated: 05/09/2026

NOTICE INVITING SPOT QUOTATION/TENDER

In view of the declaration of the Silchar Municipal Election-2026 by the Assam State Election Commission vide Memo No. SEC/72/2022/243, dated 02-09-2026, and in the interest of ensuring timely arrangements for the smooth and successful conduct of the election, Spot Quotation/Tender is hereby invited from reputed registered firms/suppliers/contractors/individuals of Cachar District having previous experience in providing similar services/supply, particularly during the recently concluded Assam Legislative Assembly Election, 2026, for undertaking various works and supply of materials required in connection with the Municipal Election-2026.

Accordingly, interested and eligible firms/suppliers/contractors/individuals are requested to submit their willingness along with quotation/rates to the undersigned on **08th September, 2026 (Tuesday), before 4:00 PM**, at the Construction/Strong Room/Electrification/Water Supply Cell, Municipal Election-2026, functioning at DDMA, Cachar, Capt. N.M. Gupta Road, Silchar.

The list of items/works for which quotations are to be submitted is enclosed as Annexure-A, B, C & D. The bidder shall submit the duly filled-in and signed Declaration in the format prescribed at Annexure-E along with the quotation.

The quotations shall be submitted item-wise, clearly mentioning the unit, quantity and quoted rate, wherever applicable. The quoted rates shall be inclusive of GST and all other applicable taxes, charges, transportation, loading/unloading and other incidental expenses, unless otherwise specified in the respective Annexure.

For the works covered under Annexure-C (Tent/Construction Works) and Annexure-D (Electrical Works), the applicable approved rates as per the APWD DSR shall be considered for evaluation and finalization of the rates.

Terms & Conditions :

1. The bidder/firm shall furnish relevant documents such as PAN Card, GST Registration Certificate, Trade Licence and Income Tax Return for the latest financial year, along with proof of experience in execution of similar works/supply, wherever applicable.
2. Preference may be given to firms having experience in similar election-related works/supply, particularly during the Assam Legislative Assembly Election, 2026.
3. The rates for the works covered under Annexure-C and Annexure-D shall be considered with reference to the applicable APWD DSR approved rates.
4. The undersigned reserves the right to accept or reject any or all quotations/tenders without assigning any reason thereof.
5. Selection shall not necessarily be based solely on the lowest rate. Ability, previous experience, quality of service/materials, availability and capacity to provide timely service shall also be taken into consideration.
6. The selected firm/supplier shall be required to provide round-the-clock service/supply, wherever required, considering the urgency and time-bound nature of the election-related activities.
7. In the event of failure of the selected firm/supplier to execute the work or supply the required materials within the stipulated time, appropriate action shall be taken as per rules, including cancellation of the work/supply order, wherever applicable.
8. Payment shall be made subject to availability and receipt of funds from the Government and after satisfactory execution/supply and submission of the required documents/bills.
9. No quotation/tender shall be accepted after the stipulated date and time of submission.
10. The selected bidder shall ensure immediate availability and supply/execution as and when requisitioned by the Construction/Strong Room/Electrification/Water Supply Cell in connection with the Municipal Election-2026.
11. The bidder shall comply with all the terms and conditions contained in the Spot Quotation/Tender Notice and the respective Annexures.
12. The duly filled-in, signed and sealed Declaration at Annexure-E shall be submitted mandatorily along with the quotation. Failure to submit the prescribed Declaration may render the quotation liable for rejection.
13. The decision of the Tender/Quotation Evaluation Committee regarding selection of the firm/supplier shall be final.

This has approval of the District Commissioner, Cachar.

Enclo : Annexure-A, B, C, D & E


Addl. District Commissioner
i/c, Construction/Strong Room/
Electrification/water supply Cell,
Municipal Election-2026

Copy to:-

1. The Election Officer, Cachar, Silchar for favour of kind information.
2. The DDIPR, BV Region, Cachar with a request to publish the Tender Notice as news item in all Print Media of the region and submit the Clips to the undersigned for record keeping purpose.
3. The DIO, NIC, Cachar with a request to upload the notice along with Annexure in the District Administration website immediately.
4. PA to the DC, Cachar for kind appraisal of the District Commissioner Cachar.


Addl. District Commissioner
i/c, Construction/Strong Room/
Electrification/water supply Cell,
Municipal Election-2026 

ANNEXURE-A

General Items

Sl. No	Items	Specifications	Unit	Rate
1.	Bleaching Powder	ISI Brand	kg	
2.	Floor Cleaner	ISI Brand	Ltr.	
3.	Phenol Liquid	ISI Brand	Ltr.	
4.	Bath Soap	ISI Brand	Pc	
5.	Hand Wash(190 ml Bottle)	ISI Brand	Nos	
6.	Iron expanded metal wire mesh	ISI Brand	Sq.mts	
7.	Plastic Bucket 5 Its	ISI Brand Plastic	Pc	
8.	Plastic Bucket 9 Its	ISI Brand Plastic	Pc	
9.	Plastic Bucket 12 Its	ISI Brand Plastic	Pc	
10.	Plastic Bucket 13 Its	ISI Brand Plastic	Pc	
11.	Plastic Bucket 15 Its	ISI Brand Plastic	Pc	
12.	Plastic Bucket 18 Its	ISI Brand Plastic	Pc	
13.	Plastic Mug 1 Its	ISI Brand Plastic	Pc	
14.	Door Window Screen	Cotton Cloth	Sq. mtr	
15.	Room Freshner	Standard	Nos.	
16.	Hand Towel	White color	Nos	
17.	Flush Cistern	ISI Brand	Nos	
18.	Soap Stand	ISI Brand	Nos	
19.	Dust Cleaner MOP	ISI Brand	Nos	
20.	Dust Pan	ISI Brand	Nos	
21.	Toilet Cleaner Brush	ISI Brand	Nos	
22.	Toilet Cleaner Liquid	ISI Brand	Ltr.	
23.	Floor Cleaning SS and Plastic	ISI Brand	Set	
24.	Floor Wiper	ISI Brand	Pcs	
25.	Spade	ISI Brand	Nos	
26.	Phool Jharu	Good Quality	Nos	
27.	Wood Scantifings	1st Class local wood	Sq.ft	
28.	GCI Sheet	(10 ft long. 0.45mm thick)	Nos	
29.	Welded Wire Mesh	2.5 mm dia wire	Sq.mts	
30.	Nail	(2.3 inches)	Kg	
31.	Ply Board	8ft x 41, 19mm thick)	PCS	
32.	Nut Bolt	(16 inch long)	Kg	
33.	Flex Printing	With Wooden Frame	sq. ft	
34.	Flex Printing	With iron Frame	sq ft	
35.	Bethua Bamboo		Nos	
36.	Barua Bamboo		Nos	
37.	Empty Cement Bags	Plastic	Nos	
38.	Sutli	(Plastic)	Kg	
39.	Binding Wire	GI Wire	Kg	
40.	Iron Shelf for EVM Storing with clamps		Kg	
41.	Dust Bin	ISI Brand	Nos	
42.	Garbage Bag for Dustbin	Big	Pkts	
43.	Garbage Bag for Dustbin	Small	Pkts	
44.	Sun Board	Vinyl	Sq	
45.	Sticker Printing		Sq. ft	
46.	Tube Light	20 Watt	No/Day	
47.	Tube Light	25 Watt	No/Day	
48.	LED Bulb	10 Watt	No/Day	
49.	Mineral Water	1ltr	Pcs	
50.	Mineral Water	2 ltr	Pcs	
51.	Mineral Water	5 ltr	Pcs	
52.	Mineral Water	20 ltr	Jar	

Addl District Commissioner
Cachar Silchar

Annexure - B

SL. NO	TENT HOUSE MATERIALS			RATE
	ITEMS	SPECIFICATIONS	UNIT	
1.	Plastic Chair with Cover(White)	Armless	No/Day	
2.	Plastic Chair without Cover(White)	Armless	No/Day	
3.	Office Chair	Arm	No/Day	
4.	Plastic Table with Cover(White)	2ft x 4ft	No/Day	
5.	Sofa Sets	3 seater	No/Day	
6.	Tea Table	Wooden	No/Day	
7.	Floor Carpet	Red/Green	Sq. ft/day	
8.	19 mm Ply Board		Pcs/day	
9.	Air Condition Machine	1.5 Ton	No/Day	
10.	Fire Extinguisher		No/Day	
11.	VIP Chair	Stainless steel	No/Day	
12.	Dustbin	Plastic Buckets 50lts	No/Day	
13.	Tarpaulin	30ft x 30ft Heavy Quality	Pcs/day	
14.	Stand Fan	Big	No/Day	
15.	Stand Fan	Small	No/Day	
16.	Air Cooler	75 L	No/Day	
17.	Air Cooler	70 L	No/Day	
18.	Table Cover	White	No/Day	
19.	Water Syntex	1000L	No/Day	
20.	Water Syntex	2000L	No/Day	
21.	Water Syntex	5000L	No/Day	
22.	Sound System with Amplifier	Supply, installation and operation of complete sound system comprising PA Amplifier	Per Set/Day	


 Addl. District Commissioner
 i/c, Construction/Strong Room/
 Electrification/water supply Cell,
 Municipal Election-2026

Annexure - C

CIVIL WORKS				
Sl. No.	DSR 2021/Analysis	Description of Items	Unit	Rate(Rs.)
1	15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 15.7.4 In cement mortar	Cum	1,698.45
2	15.36	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.	Kg	30.35
3	15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :15.12.1 Of area 3 sq. metres and below	Each	302.70
4	15.12.2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : 15.12.2 Of area beyond 3 sq. metres	Each	414.55
5	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Cum	253.95
6	2.28.1	Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. 2.28.1 All kinds of soil	Sqm	28.15
7	2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	2,161.20
8	2.80	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 2.8.1 All kinds of soil.	Cum	286.85
9	4.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	7,365.15

10	4.20	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 4.2.3 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	9,375.20
11	13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	Sqm	442.75
12	6.10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: 6.1.1 Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	6,882.00
13	6.40	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.1 Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	8,512.10
14	6.12	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : 6.12.1 Cement mortar 1:3 (1 cement : 3 coarse sand)	Sqm	862.90
15	6.13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. 6.13.1 Cement mortar 1:3 (1 cement :3 coarse sand)	Sqm	1,043.10
16	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 9.1.2 Sal wood	Cum	1,06,720.85

17	26.87	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm ² , modulus of elasticity 850 N/mm ² and resistance to spread of flame of Class A category with property of being termite/ borer proof, water/moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. 26.87.2 35 mm thick	Sqm	4,556.05
18	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	1,063.45
19	11.41A.3	Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm	Sqm	1,311.05
20	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: 17.1.1 White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	5,781.35
21	17.3	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : 17.3.1 W.C. pan with ISI marked white solid plastic seat and lid	Each	6,941.30

22	17.6	Providing and fixing one piece construction white vitreous china squatting plate with an integral longitudinal flushing pipe, white P.V.C. automatic flushing cistern, with fittings, standard size G.I. / PVC lush pipe for back and front flush with standard spreader pipes with fittings, G.I. clamps and C.P. brass coupling complete, including painting of fittings and cutting and making good the walls and floor etc. wherever required : 17.6.1 Single squatting plate with 5 litre P.V.C. automatic flushing cistern	Each	7,752.60
23	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: 17.7.1 White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	3,392.85
24	17.31	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Each	1,411.15
25	17.71	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	Each	146.30
26	18.54	Providing and fixing PTMT bib cock of approved quality and colour. 18.54.1 15mm nominal bore, 86 mm long, weighing not less than 88 gms	Each	109.85
27	18.55	Providing and fixing PTMT stop cock of approved quality and colour. 18.55.1 15 mm nominal bore, 86 mm long, weighing not less than 88 gms	Each	103.15
28	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	litre	9.70
29	16.12	Dry brick pitching half brick thick in drains including supply of bricks and preparing the surface complete : 16.12.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Sqm	607.20

30	17.10.1	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : 17.10.1 Kitchen sink with drain board 17.10.1.1 510x1040 mm bowl depth 250 mm (to be used for wash basin in temporary works)	Each	6,008.45
31	21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): 21.3.2 With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	Sqm	1,325.55
32	21.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer in-charge. 21.2.1 Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side (For blocking glass doors/windows)	Sqm	965.10
33	13.26	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	214.30
34	13.43	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : 13.43.1 Water thinnable cement primer	Sqm	64.45
35	13.42	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work	Sqm	92.75
36	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: 17.7.1 White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	3,392.85
37	21.13	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	Each	449.55

38	18.2	Providing and fixing Polyethelene-Aluminium-Polyethelene PE-ALPE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge. Concealed work, including cutting chases and making good the wall etc. 18.2.4 2532 (32 mm OD) pipe	Metre	747.85
39	18.2	18.2.1 1216 (16 mm OD) pipe	Metre	513.75
40	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 18.9.10 150 mm nominal dia Pipes	Metre	5,871.25
41	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 18.9.7 65 mm nominal dia Pipes.	Metre	1,576.90
42	16.78	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. 16.78.3 With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	Cum	2,612.95
43	10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 10.25.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	142.30

44	CE Approved rate	Hire charge of erection, fitting and fixing of steel tubular structure(hanger) made with 50mmdia MS tube truss frame made with two lines at top and bottom in curved manner of different sizes with 1.20m and 2.40m sections fitting with 6 mm thick M.S. plate joint in both faces and providing diagonal cross bracing in between the pipes of 25 mm dia. of 2 nos. & 8 nos. respectively fitted the frames with one another boltings with 50 mm long, 16 mm dia. bolt & nut, the lower most frame to be fixed on base plate of size (1.20m x 0.40m x 0.012m), the truss of height 8.00m to be placed at an interval of 3.00m with 50mm dia M.S. Tube purlins 40 nos. horizontally to cover 32.00m curvature length along the truss with bolt & nut including carriage of materials at site removing the same after the function is over as directed and specified and complete. (All the materials are contractor's property).	sqm	288.00
45	Analysis 1	Construction of temporary pandal with 100 to 150mm dia Baruah bamboo posts/post plates, Bathua Bamboo Purlin and Bracing with G.C.I sheet Roofing Completed as directed and specified. (All the materials are contractor's property)	Sqm	744.00
46	Analysis 2	Construction of partition wall providing wooden frame, partly 12mm thick prelaminate particle board and partly expanded metal 20x60 mm	Sqm	1,085.84
47	CE Approved rate	Providing bamboo barricade to satisfy the requirement to ensure proper security by making the field by semi circular and other lines as per requirement and plotting the position with line making sector wise as per drawing digging holes for fixing the ground posts minimum dia 75mm in proper position (including return filling properly) at a distance of 1.5m. The size of post being 1.95cm (1.20m above ground and 0.75m below ground grooving properly for existing of horizontal round bamboo railing minimum 75mm dia brought to proper shape fitting at a distance 45 cm above ground in lines and tying regularly coir rope as per requirement of security including local carriage of materials within two coats of lime washing as per direction and dismantling and removal of materials after the function. (Bamboo and coir rope are contractor property).	RM	65.00
48	Analysis 6	Construction of temporary watch tower providing baruah/ bhaluka bamboo ties, braces, machang, marulis, ladders, rafters, purlins, rails, including fitting and fixing of G.S sheet roofing etc complete.	nos.	19,161.00
49	CE Approved rate	Providing bamboo drop gate with bhaluka bamboo post of ht. 1.8m driven on G.L and 0.9m below the G.L. 2 nos. Post in one end --as directed	nos.	1,521.61

50	CE Approved rate	Kutchi design cloth decoration in ceiling of the pandal and side decoration of the pan dal with kutchi design cloth etc. complete as directed .(All Materials are contractors property.)	Sqm	98.00
51	CE Approved rate	Construction of view cutters made of tricolour cloth fixed with bamboo frame and wooden post etc. & removal of the same after the function after all carriage . (The bamboo and wooden beads cloth will be contractor property after the function)	Sqm	135.00
52	CE Approved rate	Construction of temporary latrine and urinal of required numbers including dismantling the same after the function	Each	14,150.00
53	CE Approved rate	Wooden flooring extra including fixing to wooden frame with iron screws, nails etc. Red port complete as directed by the dept. including dismantling of the same after the function is over (All the dismantled Materials will be contractors property as the salvage value is considered)	Sqm	511.34
54	CE Approved rate	Fitting and fixing PVC fire resistant tarpoline over the steel roof truss frame and plastic rope netting and laying the tarpoline with plastic rope with the frame including carriage of materials and removing the same after the function as directed and specified. (all the materials are contractor's property)	Sqm	105.00
55	CE Approved rate	Providing GCI sheet walling withn Bhaluka bamboo dressed post @1.50m to 2.00m C/C driven atleast 0.60m with 4nos of horizontal jati Bamboo tied with wire GI wire etc. complete as directed including cost of carriege for construction as well as dismentalling after the pramme is over.(The dismental materials such as bamboo and GCI sheet will be contractor's property)	Sqm	576.00

05/09/20
 Junior Engineer
 PWD Silchar & Udharbond
 Territorial Bldg. Sub-Divn. Silchar

10/09/20
 Asstt. Executive Engineer
 PWD Silchar & Udharbond
 Territorial Building Sub-Division Silchar

C/S
05/09/20
 Addl District Commissioner
 Cachar Silchar

ESTIMATE

Name of Work:- Temporary Electrical works in connection with Silchar Municipal Corporation Election, 2026

SL. NO.	SOR'13-14	DESCRIPTION	UNIT	RATE
1	40.1	Hire charge of 1x40 w patty type tube light fittings with tube including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Installation charge)	E/day	31.00
2	40.5	Hire charge of 250/400/500/1000 watt flood light luminaries complete (halogen/Sodium vapour/Metal halide with bulb including Wiring with 2x4 sq mm p v c insulated aluminium in open system as directed by the Deptt (Installation charge)	E/day	169.00
3	40.8	Hire charge of ceiling fan fittings with all accessories including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Installation charge)	E/day	224.00
4	40.9	Hire charge of wall fan fittings with all accessories including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Installation charge)	E/day	224.00
5	40.11	Hire charge of pedestal fan fittings with all accessories including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Installation charge)	E/day	224.00
6	40.12	Hire charge of main /sub main line with the p v c insulated aluminium conductor cable in open system complete with drawing cable as directed by the Deptt (Installation charge)		
		a. 2x2.5 sq mm	M/day	13.00
		c. 2x6 sq mm	M/day	13.00
7	40.13	Hire charge of underground armoured cable including drawing of cable as directed by the Deptt (Installation charge)		
	40.13.3	35 sq mm p v c insulated aluminium conductor cable 3.5 core	M/day	43.00
	40.13.5	e. 70 sq mm p v c insulated aluminium conductor cable 3.5 core	M/day	43.00
8	40.14	Hire charge of SPN switch fuse unit which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Recurring charge) (Installation charge).		
	40.14.2	.32 Amp capacity	Each/day	87.00
9	40.15	Hire charge of TPN switch fuse unit which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Installation charge).		
	40.15.2	b. 63 Amp capacity	Each/day	124.00
10	40.17	Hire charge of 4 pole bus bar chamber which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Installation charge)		
	40.17.2	b. 200 Amp capacity , 4 pole	Each/day	124.00
11	40.20	Hire charge of Change over Switch which should be fitted on wooden /M. S frame of the following capacity as directed by the Deptt (Installation charge)		

	40.20.2	200 amps TPN MCCB	Each/day	275.00
12	40.18	Hire charge of MCB DB which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Installation charge)		
	40.18.1	4 WAY SP MCB DB	Each/day	87.00
	40.18.3	4 WAY TP MCB DB	Each/day	124.00
13	40.19	Hire charge of MCCB enclosure which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Installation charge)		
	40.19.2	b. 200 amps TPN MCCB	Each/day	275.00
	40.19.3	c. 100 amps TPN MCCB	Each/day	275.00
14	40.21	Hire charge of earth station complete with G I pipe ,6 S W G I cable, salt, charcoal etc. as reqd as directed .	Each/day	179.00
	40.24	Hire charge of D G set per KVA (Installation charge)	per KVA	70.00
15	40.25	Hire charge of 1x40 w patty type tube light fittings with tube including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Recurring charge)	Each/day	15.00
16	40.26	Hire charge of 500 w flood/halogen light fittings with bulb including Wiring with 2x4 sq mm p v c insulated aluminium in open system as directed by the Deptt (Recurring charge)	Each/day	37.00
17	40.29	Hire charge of 250 w metal halide flood/street light fittings with bulb including Wiring with 2x4 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Recurring charge)	Each/day	129.00
18	40.32	.Hire charge of ceiling fan fittings with all accessories including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Recurring charge)	Each/day	64.00
19	40.33	Hire charge of wall fan fittings with all accessories including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Recurring charge)	Each/day	70.00
20	40.35	Hire charge of pedestal fan fittings with all accessories including Wiring with 1.5 sq mm p v c insulated aluminium conductor cable in open system as directed by the Deptt (Recurring charge)	Each/day	77.00
21	40.36	Hire charge of main /sub main line with the p v c insulated aluminium conductor cable in open system complete with drawing cable as directed by the Deptt (Recurring charge)		
	40.36.1	a. 2x2.5 sq mm	M/day	1.00
	40.36.3	c. 2x6 sq mm	M/day	1.00
22	40.37	Hire charge of underground armoured cable including drawing of cable as directed by the Deptt (Recurring charge)		
	40.13.3	35 sq mm p v c insulated aluminium conductor cable 3.5 core	M/day	5.00
	40.13.5	70 sq mm p v c insulated aluminium conductor cable 3.5 core	M/day	6.00
23	40.38	Hire charge of SPN switch fuse unit which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Recurring charge).		
	40.38.2	32 Amp capacity	Each/day	37.00

24	40.39	Hire charge of TPN switch fuse unit which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Recurring charge).		
	40.39.2	b 63 Amp capacity	Each/day	75.00
25	40.41	Hire charge of 4 pole bus bar chamber which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Recurring charge).		
	40.41.2	b. 200 Amp capacity , 4 pole	Each/day	72.00
26	40.43	Hire charge of MCCB enclosure which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Recurring charge).		
	40.43.2	b. 200 amps TPN MCCB	Each/day	113.00
27	40.44	Hire charge of MCCB which should be fitted on the existing MCCB enclosure of the following capacity as directed by the Deptt (Recurring charge).		
	40.44.2	b. 200 amps TPN MCCB	Each/day	276.00
	40.44.3	c. 100 amps TPN MCCB	Each/day	215.00
28	40.42	Hire charge of MCB DB which should be fitted on wooden /M/ S frame of the following capacity as directed by the Deptt (Recurring charge).		
	40.42.1	a. 4 WAY SP MCB DB	Each/day	49.00
	40.42.3	c. 4 WAY TP MCB DB	Each/day	57.00
29	40.45	Hire charge of earth station complete with G I pipe ,6 S W G I cable, salt, charcoal etc. as reqd as directed (Recurring charge).	Each/day	20.00
30	40.48	Hire charge of D G set (125KVA) 3nos.	Per/KVA	113.00
31		Hire Charge of Supplying and fixing of Inverter Set	Each	1000.00
32		Hire Charge of Supplying and fixing of Generator Battery 150Ah	Each	350.00
33		Hire charge of Package Type Air Conditioner Machine.	Tn/Day	1980.00
34		Installation Charge	Tn	120.00
		Transportation charge (To & fro)	Tn/Day	4000.00
		Operation charge	Day	806.00
		Generator Operator(6nos. For 20Days in Three Shift)	Day	806.00
35	DSR'22 1008	Electrician	Day	


 Asstt. Executive Engineer PWD.
 Silchar Electrical Sub-Division
 Silchar


 Addl District Commissioner
 Cachar Silchar

DECLARATION

I, _____, proprietor/authorized representative of
 _____, a registered Government
 distributor/supplier/contractor/firm, hereby solemnly declare and undertake that:

1. I have carefully read and understood all the terms, conditions, specifications and requirements contained in the Spot Quotation/Tender Notice and its Annexures issued by the Construction/Strong Room/Electrification/Water Supply Cell, Municipal Election-2026, and undertake to comply with the same in letter and spirit.
2. I undertake to provide the required materials/services/work as and when requisitioned by the Administration, including round-the-clock service/supply wherever required, keeping in view the urgency and time-bound nature of the Municipal Election-2026.
3. I understand that any failure on my part to provide the required materials/services/work within the stipulated time or as per the directions of the Administration may result in cancellation of the work/supply order and other appropriate action as per rules/law.
4. I hereby declare that all information, documents, certificates, experience details, financial particulars and other supporting documents submitted by me along with the quotation are true, genuine and correct to the best of my knowledge and belief.
5. I further declare that I am not debarred, blacklisted or otherwise ineligible to participate in any Government procurement/tender process and that I have not been involved in any fraudulent, corrupt or anti-competitive practice in connection with any Government contract, work or supply.
6. I understand and accept that any false statement, misrepresentation, concealment of material facts or submission of forged/incorrect documents may lead to rejection/disqualification of my quotation and/or cancellation of the work/supply order, besides any other action permissible under the applicable rules/law.
7. I undertake to maintain close coordination with the District Administration and the Construction/Strong Room/Electrification/Water Supply Cell and extend necessary cooperation for the smooth and successful conduct of the Municipal Election-2026.
8. I further agree that the decision of the competent authority regarding selection/acceptance of the quotation and allocation of work/supply shall be final and binding upon me.

Place: _____

Date: _____

For: _____

Signature: _____

Name: _____

Designation: _____

Firm/Agency Name: _____

Phone No.: _____

Address: _____

Seal of the Firm/Agency